

MAY 07 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
1996 DEC 18 AM 11:15

For corners in COMMISSION

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 40N R 29W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN MI 49801

9

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 8 November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7; Section Corner common to Sections 13, 14, 23, and 24, T40N, R29W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7; Section Corner common to Sections 13, 14, 23, and 24, T40N, R29W;

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-17-96
RAP
COUNTY REPRESENTATIVE

Found a 2" diameter iron pipe at ground level alongside of which is the 1" x 42" galvanized iron pipe with 4" brass cap as set by Mr. DeLaMater in 1953. This monument was found to be in agreement with Mr. DeLaMater's new bearing trees as described in Part A. Replaced Mr. DeLaMater's monument with a standard county monument set inside the 2" diameter iron pipe. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7; Section Corner common to Sections 13, 14, 23, and 24, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

Set 7" spike	NW/side	5" Cedar	N38°E	27.83'
Set 7" spike	NE/side	6" Cedar	S55°E	18.84'
Set 7" spike	NW/side	6" Black Spruce	S35°W	17.47'
Set 7" spike	NE/side	6" Cedar	N51°W	14.68'
		Location Post	North	3.0'

All of the above new bearing trees are marked with upper and lower blazes.

The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.



Signed by Michael Mileski

Date 3 Dec 1996

Surveyor's Michigan License No. 39091

Bk. 17M pp 7 & 8