

MAR 03 1998

RECORDED

1997 DEC 10 PM 3:57

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dickinson (County)

Located in:

Corner Code #

Norway Twp.

Table with 3 columns: Item description, Corner Code (T/S), and Range/Bearing (e.g., 40N R 29W). Includes items for Public Land Survey, Property Controlling, and Miscellaneous.

REGISTER OF DEEDS DICKINSON COUNTY

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13, used for recording deed information.

I, Robert F. Perkins, in a field survey on Sept. 17, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1 Northeast Corner, Section 1 Post by James H. Mullett, D.S. Oct. 12, 1848 Original Bearing Trees: Fir 6" S67°E 10 Lks. Cedar 15" S27°W 20 Lks.

M-2 East 1/2 Corner, Section 1 Post by James H. Mullett, D.S. Oct. 12, 1848 Original Bearing Trees: Hemlock 15" N34°W 26 Lks. Hemlock 15" S84°E 26 Lks.

FILED BY THE DICKINSON COUNTY PEER GROUP AS THE OFFICIAL RECORDER UNDER MICHIGAN PUBLIC ACT 1990 AT A MEETING HELD ON

12-9-97 RFP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: COUNTY REPRESENTATIVE

M-1 No Evidence of Original Corner or Accessories Found. Field chained North 3353' from 1/2 Corner and found 1" Iron Pipe with 4" D.N.R. Brass Cap Set by D.C. DeLaMater, RLS in 1955. 1955 Bearing Tree: Cedar 12" S35°W 24 Lks. (Old Report #27)

M-2 No Evidence of Original Corner or Accessories Found. Found 1" Iron Pipe with 4" D.N.R. Brass Cap Set by D.C. DeLaMater, RLS in 1955. 1955 Bearing Trees: Maple 8" S80°W 19 Lks. Maple 6" S83°E 24 Lks. (Old Report #26)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Found and Accepted above Described Pipe Monument. New Witnesses: Cedar 18" S35°W (M.B.) 15.62' (1955 B.T.) Fir 6" S58°E (M.B.) 5.20' Nail/Tag Cedar 14" S78°W (M.B.) 48.28' Nail/Tag Spruce 8" S10°W (M.B.) 31.50' Nail/Tag Carsonite Marker North 1.0'

M-2 Found and Accepted above Described Pipe Monument. New Witnesses: Maple 8" N05°W 17.15' Nail/Tag * Maple 12" S83°E 15.95' Nail/Tag * Maple 12" S80°W 12.80' Tree Maple 10" S22°W 26.68' Nail/Tag Carsonite Marker South 1.0' * Existing 1955 B.T.

Signed by [Signature]

Date Nov. 19, 1997

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

LIBER 0025318

