

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 10 PM 3:57

For corners in	Located In:	Corner Code #
Dickinson (County)		
Norway Twp.		
1. Public Land Survey	T 40N R 29W	M-3
	T R	M-4
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

REGISTER OF DEEDS
DICKINSON COUNTY
RON MOORE 2401 4000

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert F. Perkins, in a field survey on Sept. 17, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3 Southeast Corner, Section 1
Post by James H. Mullett, D.S.
Oct. 12, 1848.
Original Bearing Trees
Cedar 10" N21°W 09 Lks.
B.Ash 12" S53°W 23 Lks.

M-4 East 1/4 Corner, Section 12
Post by James H. Mullett, D.S.
Oct. 12, 1848.
Original Bearing Trees
Cedar 10" N53°W 27 Lks.
Hemlock 10" S56°E 17 Lks.

ACCEPTED BY THE DICKINSON COUNTY
SURVEYOR GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
74 OF 1970 AT A MEETING HELD ON
12-9-97
RFP
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found Stump of Black Ash B.T.
Found 1" Iron Pipe with 4" D.N.R.
Brass Cap Set by D.N.R. in 1952.
1952 Bearing Trees:
Hemlock 10" N62°W 18 Lks.
Spruce 14" S15°E 48 Lks.
(Old Report #25)

M-4 No Evidence of Original Corner
or Accessories Found.
Field chained 2670' South from
Section Corner and found 1" Pipe with
4" D.N.R. Brass Cap set by Billy
Buckler, RLS in 1956.
1956 Bearing Trees:
Cedar 14" Squared at Corner
Cedar 14" S52°W 20 Lks.
(Old Report #24)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Found and Accepted above described
Pipe Monument.
New Witnesses:
Y.Birch 8" S13°E (M.B.) 17.52' Nail/Tag
Y.Birch 8" N78°E (M.B.) 33.28' Nail/Tag
Maple 4" N23°E (M.B.) 36.28' Nail/Tag
Ash 8" S31°W (M.B.) 11.80' Nail/Tag
Carsonite Marker East 0.7'

M-4 Found and Accepted above described
Pipe Monument.
New Witnesses:
Ash 12" N09°W (M.B.) 12.90' Nail/Tag
Maple 14" S62°E (M.B.) 25.54' Nail/Tag
Cedar 10" N78°W (M.B.) 22.00' Nail/Tag
* Cedar 18" S70°W (M.B.) 12.90' Nail/Tag
Carsonite Stake East 1.0'
* Existing 1956 B.T.

Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date Nov. 19, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
REVISED MAY 14, 1975
NO. 1997 JAN. 1997

