

SURVEY & REMONUMENTATION

MAY 07 1997

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:15

For corners in **COMMISSION**

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T40N R29W</u>	<u>M-7*</u>
	<u>T40N R28W</u>	<u>A-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 DICKINSON COUNTY
 (IRON MOUNTAIN, MI. 49801)

11

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on 24 October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-7; Section Corner common to Sections 13 and 24, T40N, R29W;
 See back of form.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-17-96
RDP
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7; Section Corner common to Sections 13 and 24, T40N, R29W;
 Found a 1" x 42" galvanized iron pipe with a 4" brass cap as set by Mr. Buckler in 1955. Mr. Buckler's monument was found to be in agreement with his new bearing trees as described in Part A. Replaced Mr. Buckler's monument with a standard county monument as described in Part C. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7; Section Corner common to Sections 13 and 24, T40N, R29W;
 Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

Set 7" spike	SE/side	7" Red Maple	N41°E	9.79'
Set 7" spike	SW/side	7" Sugar Maple	S60°E	38.90'
Set 7" spike	W/side	10" Sugar Maple	S20°E	29.59'
Set 7" spike	N/side	12" Sugar Maple	S59°W	54.59'
		Location Post	North	3.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

* This corner is also A-7 of T40N, R28W.



Signed by [Signature]
 Surveyor's Michigan License No. 39091

Date 3 Dec 1996
 Bk. 17M pp 1 & 2

Liber 2 Page 233