

SURVEY & MONUMENTATION

MAY 07 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:15

COMMISSION

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T40N R29W

M-9*

T40N R28W

A-9

2. Property Controlling in Section

S ___ T ___ R ___

3. Miscellaneous

S ___ T ___ R ___

Property in Sec.

S ___ T ___ R ___

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

15

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on 7 November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9; Section Corner common to Sections 24 and 25, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9; Section Corner common to Sections 24 and 25, T40N, R29W;

Found a 1" x 42" galvanized iron pipe with a 4" brass cap as set by Mr. Buckler in 1955 and in agreement with the remains of his new bearing trees as described in Part A. Replaced with a standard county monument described in Part C. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9; Section Corner common to Sections 24 and 25, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

Set 7" spike	S/side	13" White Spruce	N83°E	25.67'
Set 7" spike	SW/side	6" Cedar	S24°E	65.43'
Set 7" spike	W/side	7" White Spruce	S43°W	12.52'
Set 7" spike	S/side	6" White Spruce	N62°W	5.52'
Set 7" spike	W/side	9" White Spruce	N22°W	24.90'
		Location Post	North	3.0'



All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

*This corner is also A-9 of T40N, R28W.

Signed by Michael Mileski

Date 3 Dec 1996

Surveyor's Michigan License No. 39091

Bk. 17M pp 28 & 29