

SURVEY &  
REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 10 PM 3:57

SECTION

For corners in  
Dickinson  
(County)

Located In:

Corner Code #

Norway Twp.

1. Public Land Survey	T	<u>40N</u>	R	<u>29W</u>	<u>M-13</u>
	T		R		<u>J-11</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

REGISTER OF DEEDS  
DICKINSON COUNTY  
40N MAPLE TWP. 1997

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert F. Perkins a field surveyor on Sept. 5, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13	Southeast Corner, Section 36	J-11	1/4 Corner
	Post by H. Brevort 1847		Post by James Mullett, D.S. 1849
	Original Bearing Trees		Original Bearing Trees
	Sugar 12" N29°W 24 Lks.		Birch 10" S66°E 19 Lks.
	Hemlock 14" N66°E 33 Lks.		Maple 10" S44°W 25 Lks.

APPROVED BY THE DICKINSON COUNTY  
PLER GROUP AS THE OFFICIAL  
UNDER MICHIGAN PUBLIC ACT  
1990 AT A MEETING HELD ON  
12-9-97  
ROIP


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13	Found 1" Iron Pipe with 4" Brass Cap D.N.R. Marker set by Billy Buckler, R.L.S. in 1961 (Old Report #620). 1961 Bearing Trees Elm 7" S04°E 167 Lks. Maple 14" N80°W 81 1/2 Lks.	J-11	W.E. Johnson, C.E. tied into 2" Iron Pipe at Cedar Post in 1934 and made B.T.'s: Cedar 6" N21°E 7.5' Hemlock 4" N31°E 12.4' Balsam 3" N78°E 11.9'  9-5-97: Found above 2" Iron Pipe and Point of Cedar Post in muck. Found Stump of B.T. Cedar 6" Corner research in 1996.
------	--	------	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13	Found above described Monument in place. New Witnesses Spruce 18" N12°E (M.B.) 9.65' Nail/Tag R.Pine 9" S06°E (M.B.) 86.43' Nail/Tag Tamarack 8" S49°W (M.B.) 54.26' Nail/Tag Carsonite Marker South 1.6' Existing 1961 B.T.: Db. Sugar Maple 30" N78°W (M.B.) 53.60'	J-11	Accepted above Pipe/Post as Best Available Evidence of Corner Location. Set 2 1/2 Stamped Re-Mon. Corner at Old Post Point.  New Witnesses: S.Maple 6" S70°W (M.B.) 25.70' Nail/Tag Cedar 8" N14°E (M.B.) 25.63' Nail/Tag Cedar 9" N68°E (M.B.) 31.58' Nail/Tag Lynn 8" S07°E (M.B.) 34.60' Nail/Tag Carsonite Marker South 1.5'
------	---	------	---

Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027



Date Nov. 19, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983