

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 40. NR. 29. W. 1.

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 9,10,15,16 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 8" Soft Maple - N 52 E - 29 Links -----

9" Balsam - S 28 W - 29 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Good measurements N & S to bottom of hill & swamp edges, and West to top of hill & rock ledge.

Corner was placed and witnessed August 4, 1954.

SURVEYORS SEAL

SIGNED

*Sean C. DeLoe*  
REGISTERED LAND SURVEYOR

DATE 2/10/54