

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Dickinson

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 ^{N.} 38 R. 29 ^{W.} W.	I 10 & I 11
2. PROPERTY CONTROLLING IN SECTION	27 T. 40 ^{N.} 38 R. 29 ^{W.} W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} S. R. ^{W.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on July 10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner I10:** Wood post Not found. No subsequent monuments found.
 Fir 10 S31W 19 Not found. No subsequent accessories found.
 Birch 6 N20E 6 Not found. No subsequent accessories found.
- Corner I11:** Wood post Not found. Found a 2" O.D. x 54" iron pipe.
 Lynn 12 S58E 11 Not found. Found new accessories as shown
 Hamlock 12 N63W 11 in C, below
- Corner 7:** Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner I10:** Re-established on line between sec. corners 39.973 ch. S and 39.473 ch. N. Comparison of measured with record distances to natural features on this section line indicates the probability of a .50 ch. mistake in the original survey in the N. half-mile. Therefore, applied this error (deficiency) to the measured N half-mile. An additional .054 ch. deficiency in the whole mile was distributed as a general average error.
- Corner I11:** Replaced a 2" O.D. x 54" iron pipe found in place as re-witnessed on 12/3/57 by B. D. Buckler, R. L. S. Position agrees with record calls to a stream and rock ledge N and foot of hill E, and location on side of a hill.
- Corner 7:** Established on line between section corner 19.737 ch. N and 1/4 corner 19.736 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses to Corner I10:** Cedar 7 N63°W (mag.) 27.2 ft. "1/4S, NBT"
 Cedar 6 S60°E (mag.) 30.1 ft. "1/4S, NBT"
- Witnesses to Corner I11:** Sugar Maple 4 N72°E (mag.) 11.8 ft. "S26, NBT"
 (By B.D. Buckler, R.L.S.) Sugar Maple 4 S29°W (mag.) 9.6 ft. "S34, NBT"
 W. Spruce 6 S53°E (mag.) 24.4 ft. "S35, NBT"
 W. Birch 5 N28 1/2°W (mag.) 11.3 ft. "S27, NBT"
- Witnesses to Corner 7:** Cedar 5 N27°W (mag.) 31.7 ft. "1/16S, BT"
 W. Spruce 14 S88°W (mag.) 36.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 29, 1973
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**