

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 29 XX W.	G 9
2. PROPERTY CONTROLLING IN SECTION	27 T. 40 N. R. 29 XX W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of origin monument and accessories and/or subsequent restoration:
- | | |
|--|---|
| Corner G 9: Wood post
Hemlock 10 N50E 12)
" 10 N63W 20) | Not found. No subsequent monuments found.
" " No subsequent accessories " ,
except as explained in B, following. |
|--|---|
- Corner 1:** Not established in original survey. May have been established, or approximately established, previously, as evidenced by N & S farm fence S of corner.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G 9:** Re-established 7/5/72 in approximate centerline of E'ly & W'ly county road in line with N & S fences going N & S from road and midway between fences going E & W on N & S sides of road. Direction and distance from probably original 1/4 corner a half mile south is consistent with other section lines in this township. U. S. G. S. topographic maps indicate road passes through section corner at this point.
- Corner 1:** Established 7/11/72 on line between Sec. Cor. 20.160 ch. W and 1/4 corner 20.160 ch. E. Corner lies in pasture N of road.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G 9:** 1" I.D. x 28" iron pipe with 4" aluminum cap, buried in road.
Sugar Maple 8 N3°W (mag.) 25.25 ft. "NBT"
⊕ chiselled on boulder top S15¼°E (mag.) 21.18 ft.
- Corner 1:** 1/2" I.D. x 28" iron pipe.
+ chiselled in rock N40¼°E 29.49 ft.
+ chiselled in rock S83¼°E 78.07 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)
FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
APPROVED AND SIGNED BY Arthur O. Enger DATE **April 12, 1973**
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581