

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ S. _____ R. _____ E. _____ W. _____	
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. <u>40</u> S. <u>XX</u> R. <u>29</u> E. <u>XX</u> W. <u>XX</u>	4, 5, & 6
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

None of these corners established in original survey. From Corner 5, a fence corner W & N bears S26°E 6.26 ch. and from Corner 4, a fence corner E & N bears S30½°W 5.52 ch. Corner 6 never established, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 4: Post placed 7/11/72 on line one-fourth of the distance between N 1/16 cor. bet. Sec. 27 & 28 and N 1/16 cor. bet. Sec. 26 & 27.

Corner 5: Post placed 7/11/72 on line one-half of the distance between N 1/16 cor. bet. Sec. 26 & 27 and N 1/16 cor. between Sec. 27 & 28.

Corner 6: Post placed 7/10/72 on line one-fourth of the distance between N 1/16 cor. bet. Sec. 26 & 27 and N 1/16 cor. bet. Sec. 27 & 28.

Note: As the N & S 1/4 line of Sec. 27 was not established, these corners may not be exactly correct according to the rules for sub-dividing a section. Users of these corners are hereby notified of this fact.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 4: 3" x 3" x 74" axe-squared cedar post.
Sugar Maple 6 S33°E (mag.) 27.2 ft. "1/16S, BT"
Sugar Maple 3 S42°W (mag.) 8.9 ft. "1/16S, BT"

Corner 5: 4" x 4" x 72" axe-squared cedar post
Red Maple 6 S13°E (mag.) 14.1 ft. "1/16S, BT"
Red Maple 7 S65°W (mag.) 10.8 ft. "1/16S, BT"

Corner 6: 4" x 4" x 48" square-sawn cedar post
Sugar Maple 6 N82°E (mag.) 19.5 ft. "1/16S, BT"
Sugar Maple 4 S51°E (mag.) 11.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY: Arthur O. Enger DATE April 12, 1973

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581