

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 29-30 W


Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 6 and 1

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 12/60 with H.S. Peterson, District Forester

WITNESSES TO CORNER..... 18" W. Pine (1/4^s NBT) N 30° W 60 1/2 Links



13" W. Pine (1/4^s NBT) N 70° E 84 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by proportionate measure between original Section

Corner to South and Rock Ledge to North. Government distance = 65.00 chains

Measured distance = 64.47 chains. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE

2/21/61