

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 29 & 30 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section corner for sections T40N 12/7 T40N
R30W 13/18 R29W

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7/26/67, Frank J. Bray

WITNESSES TO CORNER..... 20" Elm (S18)(NBT) S 05° E, 61 Links



9" Elm (S7)(NBT) N 78° E, 12½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Established using old down blazed & notched cedar facing corner as set measurements to stream crossings to north and east. Summit of hill to south and swamp edge and hill to west check well with original notes. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10-13-67
REGISTERED LAND SURVEYOR