

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 40N R 29W F11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Nov 06 2000

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F11) Quarter corner common to Sections 28 and 33. 1849: James H. Mullett, DS. Set wood post witnessed by: Cedar 10 S70W 27 lks.; 8" Ash 6 N05E 19 lks. 1932: Dickinson County Road Commission. Squared cedar stake witnessed by: 8" Elm S86-00E 21.0'; 10" Elm S29-30W 15.2'; 6" Elm S86-30W 21.1'; 6" Elm N37-00W 16.1'. 1983: James H. Moore, LS. Set 1 1/2" iron pipe at proportionate distance between section corners witnessed by: 6" Ash N80W 8.62'; 4" Ash N25E 18.52'; Conc. monument S75E 77.86'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F11) No evidence of original survey found. Found Moore's iron pipe and witnesses as described. Local long-time landowner claims concrete monument used as witness by Moore was in existence when he was a child, and has always been considered as the corner. Concrete monument is at the intersection of ancient fences south and west, the same as monument found at the section corner one half mile east, and there is a concrete monument recorded as the section corner one half mile west. Measured east from Moore's pipe 144 feet to right bank of stream (GLO-1.06 chains-70 feet), measured east from concrete monument 75 feet to bank of stream. Checking for DCRC witnesses, found remains in proper position for two of the witnesses from the concrete monument (stump N37W 16'; old wood S29W 15'). Distance east to the southeast corner of Section 28 measured 2570.24 feet, DCRC survey notes show 2577.1 feet. Distance west to southwest corner measured 2719.12 feet, DCRC survey notes show 2718.3 feet. Based on the evidence found, Moore's pipe was rejected as the quarter corner position, the concrete monument was re-witnessed as found, a plastic cap "MI DNR 37270" was set on it, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F11) conc. monument w/ plastic cap  
14" Ash N40E 38.85' (1/4S,NBT)  
07" Cedar S31E 12.05' (1/4S,NBT)  
09" Ash S24W 18.9' (1/4S,NBT)  
10" Cedar N70W 17.15' (1/4S,NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
Surveyor's Michigan License No. 37270

Date \_\_\_\_\_

For the Michigan Department of Natural Resources - Forest Management Division