

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>29W</u>	<u>H11</u>
	T <u>40N</u> R <u>29W</u>	<u>I10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I10 Sep 26 2000  
 H11 Oct 04 2000

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(H11) Quarter corner common to Sections 27 and 34. 1849: James H. Mullett, DS. Set wood post witnessed by: Beech 6 N02W 8 lks.; Beech 8 S23W 33 lks.  
 (I10) Quarter corner common to Sections 26 and 27. 1849: James H. Mullett, DS. Set wood post witnessed by: Fir 10 S31W 19 lks.; Birch 6 N20E 6 lks. 1972: Art Enger, RLS. Set DNR monument by single proportion (applying an assumed error in the north half mile) witnessed by: Cedar 7 N63W 27.2'; Cedar 6 S60E 30.1'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(H11) No evidence of original survey or subsequent restoration found. Corner position re-established mid-point and on-line between the Southeast and Southwest corners of Section 27, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.  
 (I10) Found Enger's monument and witnesses as described. Leave swamp call 0.5 chains north fits fairly well. Measured N58W 27.3' to notch in 12" Cedar (record Cedar 7 N63W 27.2'); measured S56E 30.05' to notch in 8" Cedar (record Cedar 6 S60E 30.1'). Monument was re-witnessed as found, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(H11) DNR monument	(I10) DNR monument
7" Sugar N27E 9.75' (1/4S,NBT)	05" Cedar N17E 14.05' (1/4S,NBT)
5" Sugar S40E 11.95' (1/4S,NBT)	08" Cedar S56E 29.95' (EX. NBT)
5" Sugar S34W 9.55' (1/4S,NBT)	07" Cedar S04W 41.55' (1/4S,NBT)
6" Sugar N71W 26.65' (1/4S,NBT)	12" Cedar N58W 27.65' (EX. NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
 Surveyor's Michigan License No. 37270

Date \_\_\_\_\_

For the Michigan Department of Natural Resources - Forest Management Division