

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>27</u> T <u>40N</u> R <u>29W</u>	<u>12</u>
	S <u>27</u> T <u>40N</u> R <u>29W</u>	<u>15</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

15 Oct 05 2000  
 12 Oct 19 2000

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12) South One-sixteenth corner of Section 27. Not set in original survey, no evidence of subsequent establishment.
- (15) West One-sixteenth corner common to Sections 27 and 34. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12) Corner position established mid-point and on-line between the South and Center Quarter corners of Section 27.
- (15) Corner position established mid-point and on-line between the Southwest and South Quarter corners of Section 27.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                                    |                                 |
|------------------------------------|---------------------------------|
| (12) DNR monument                  | (15) DNR monument               |
| 10" Basswood N20E 26.3' (1/16S,BT) | 7" Sugar N15E 17.75' (1/16S,BT) |
| 06" Sugar S73E 27.3' (1/16S,BT)    | 5" Sugar S68E 9.9' (1/16S,BT)   |
| 05" Ironwood S26W 34.3' (1/16S,BT) | 4" Sugar S33W 3.9' (1/16S,BT)   |
| 08" Sugar N75W 12.25' (1/16S,BT)   | 8" Sugar N64W 16.9' (1/16S,BT)  |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
 Surveyor's Michigan License No. 37270

Date \_\_\_\_\_

For the Michigan Department of Natural Resources - Forest Management Division