

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>27</u> T <u>40N</u> R <u>29W</u>	<u>11</u>
	S <u>28</u> T <u>40N</u> R <u>29W</u>	<u>14</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

14 Aug 31 2000
 11 Oct 19 2000

I, Paul R. Bressette, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (11) Southwest One-sixteenth corner of Section 27. Not set in original survey, no evidence of subsequent establishment.
- (14) South One-sixteenth corner common to Section 27 and 28. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (11) Corner position established at the intersection of the south and west one-sixteenth lines of Section 27.
- (14) Corner position established mid-point and on-line between the Southeast and East Quarter corners of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------------------|-----------------------------------|
| (11) DNR monument | (14) DNR monument |
| 6" Beech N33E 25.2' (1/16S,BT) | 08" Hemlock N81E 25.7' (1/16S,BT) |
| 9" Basswood S24E 60.0' (1/16S,BT) | 08" Oak S58E 25.2' (1/16S,BT) |
| 4" Aspen S31W 6.4' (1/16S,BT) | 08" Maple S24E 19.05' (1/16S,BT) |
| 4" Ash N59W 35.1' (1/16S,BT) | 18" W.Pine S50W 39.2' (1/16S,BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division