

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 in Section

S 28 T 40N R 29W 13
 S 28 T 40N R 29W 16

3. Miscellaneous
 Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 06 2000

I, Paul R. Bressette, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (13) Southeast One-sixteenth corner of Section 28. Not set in original survey, no evidence of subsequent establishment.
- (16) East One-sixteenth corner common to Sections 28 and 33. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (13) Corner position established at the intersection of the south and east one-sixteenth lines of Section 28.
- (16) Corner position established mid-point and on-line between the Southeast and South Quarter corners of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------------------|-----------------------------------|
| (13) DNR monument | (16) DNR monument |
| 05" Hemlock N73E 22.9' (1/16S,BT) | 13" Spruce N27E 29.3' (1/16S,BT) |
| 11" Cedar S31E 8.25' (1/16S,BT) | 05" Spruce S16E 28.1' (1/16S,BT) |
| 06" Hemlock S60W 36.05' (1/16S,BT) | 10" Spruce S55W 16.25' (1/16S,BT) |
| 11" Hemlock N45W 50.05' (1/16S,BT) | 06" Spruce N57W 37.5' (1/16S,BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division