

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>29W</u>	<u>14</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> 2 </u> T <u>40N</u> R <u>29W</u>	<u> 8 </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

8 Sep 11 2000
 I4 Oct 24 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3				2	1			
3												
4	7	8	9	10				11	12			
5												
6	18	17	16	15				14	13			
7												
8	19	20	21	22				23	24			
9												
10	30	29	28	27				26	25			
11												
12	31	32	33	34				35	36			
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(I4) Quarter corner common to Sections 10-11. Established in 1849 by James Mullett. North btwn Secs. 10 & 11...40.00 Set quarter Sec. post on summit. W. Pine 14 S23E 17, Hemlock 4 S67W 07...80.00 Set post corner Secs 2,3,10,11.
 (8-Sec. 2) West 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I4) Original post and accessories were not recovered. The location of the topographic calls along this line is substantially inharmonious with the original record. Retracement in this township shows that the measurements along the lines were poorly made, particularly along some of the M-S lines. We observed differences with the original record of over 300'/mile. Though the ledge mentioned in the original record as being 2.5 chains south of this corner was recovered, the poor quality of the measurements precluded absolute reliance upon the topographic feature calls for the reestablishment of this corner. Accordingly, I monument the corner midway and on a line of mean true bearing between Section corners 2715.4' north and south, being proportionate to the original record measurement.
 (8-Sec. 2) Established the corner midway and on a straight line between Center of Section 1325.0' east and Quarter corner 1325.0' west. From the position thus established, I found a metal "T" fence post, not of record, S50W, 75 ft. distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I4) Set 1" ID iron pipe with 4" aluminum MDNR cap. Blazed and scribed: 3" W.Ash S50E 10.1' "1/4S NBT" 4" W.Spruce S20E 25.4' do 13" R.Pine S23W 40.0' do 10" R.Oak S55W 67.1' do Squared a 3" aspen S55E 2.5' to center. Bearings are magnetic. Distances to notch in lower blaze. The mon. is set in a 2ft. dia. rock mound.	(8) Set 1" ID iron pipe with 4" aluminum MDNR cap. Blazed and scribed: 7" Sugar N16E 45.7' "1/16S BT" 13" Y.Birch S83W 56.4' do 9" Y.Birch S36W 58.0' do 5" Balsam S33E 16.9' do Bearings are magnetic. Distances to notch in lower blaze.
--	---



Signed by Stephan J. Szyszkoski Date 1/16/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division