

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Dickinson  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey      T\_\_\_ R\_\_\_ \_\_\_\_\_  
                                   T\_\_\_ R\_\_\_ \_\_\_\_\_  
                                   T\_\_\_ R\_\_\_ \_\_\_\_\_  
                                   T\_\_\_ R\_\_\_ \_\_\_\_\_

2. Property Controlling    S 4 T 40N R 29W      4  
 in Section                    S\_\_\_ T\_\_\_ R\_\_\_ \_\_\_\_\_  
 3. Miscellaneous            S\_\_\_ T\_\_\_ R\_\_\_ \_\_\_\_\_  
 Property in Sec.            S\_\_\_ T\_\_\_ R\_\_\_ \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 06 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (4-Sec. 4) Northwest 1/16 corner, Section 4. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(4-Sec. 4) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, I found a 1.5" dia. iron pipe, not of record, N85W 76 ft. distant.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(4) Set 1" ID iron pipe with 4" aluminum  
 MDNR cap. Blazed and scribed:  
 4" dbl Sugar N44E 16.6' "1/16S BT"  
 4" Sugar S38E 23.0' do  
 4" Maple S16W 8.6' do  
 5" Sugar N30W 21.5' do  
 Sqd cedar post adjacent. Bearings are  
 magnetic. Distances are to notch in  
 lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 3/29/01

For the Michigan Department of Natural Resources - Forest Management Division