

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S 5 T 40R 29W _____ 10
 in Section S 5 T 40R 29W _____ 11

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

11 Mar 15 2001
 10 Dec 04 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (10-Sec. 5) South 1/16 corner between Sec. 5 & 6. Not established in the original survey.
 (11-Sec. 5) Southwest 1/16 corner, Section 5. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 5) I established the corner midway and on a line of mean true bearing between Section and Quarter corners 1304.5' south and north, respectively. From the position thus established, I found a 1" ID iron pipe, not of record, N36E, 0.52 ft. distant.
 (11-Sec. 5) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1" ID iron pipe with 4" aluminum MDNR cap. Blazed and scribed: 10" Hemlock N03E 25.6' "1/16S BT" 13" Y. Birch S51E 5.7' do 9" Cedar S20W 59.8' do 14" Cedar N89W 41.0' do Sqd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	(11) Set 1" ID iron pipe with 4" aluminum MDNR cap. Blazed and scribed: 8" Spruce N15W 33.2' "1/16S BT" 10" Sugar N89E 73.9' do 8" Sugar S43E 64.2' do 12" Hemlock N80W 71.1' do Sqd cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 3/29/01

For the Michigan Department of Natural Resources - Forest Management Division