

RECORDED

1998 DEC 14 PM 12: 24

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #

Breitung Twp.  
1. Public Land Survey

T 40NR 30W

T R

T R

T R

T R

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

A-2  
B-5  
REGISTER OF DEEDS  
DICKINSON COUNTY  
REGISTER OF DEEDS STAMP & FILE NUMBER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert F. Perkins, in a field survey on Aug. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-2 West 1/4 Corner Section 6  
Post by H. Brevort, D.S. 1848  
Original Bearing Trees  
Aspen 3" S15°E 04 Lk.  
Cherry 3" N80°W 08 Lk.  
1978 E.C. Muller, P.S. & E. Kaziaka, P.S.  
find 3/4" Iron Rod in Road Centerline and  
Record same on Certificate #181.

B-5 1/4 Corner Common to Sections 7  
Post by James H. Mullett, D.S. 1849  
Original Bearing Trees  
Birch 3" S44°E 24 Lk.  
Birch 3" S60°E 20 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 No Evidence of Original Corner  
or its Accessories Found.  
Found 1978 Bearing Trees:  
Oak 5" N16°E 46.87'  
Maple 6" S21°E 13.47' (Stump & Nail)  
Failed to find 3/4" Iron Rod.  
Probably Lost in Road Construction.

B-5 No Evidence of Original Corner  
or Accessories Found.  
Found 1" Sq. Iron Bar with 2 Existing  
BT's as Noted on Old Corner Report  
#826 by J. Smallwood dated 4-16-64.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 Set 3 1/2" Stamped D.C. Remon. Corner from  
2 Found 1978 BT's Noted in B.  
New Witnesses  
P.Pole #85-22742 N48°W(M.B.) 24.94' Nail/Tag  
P.Pole #85-22709 S18°W(M.B.) 57.50' Nail/Tag  
Oak 5" N16°E(M.B.) 46.87' Ex. B.T.  
Set 2 1/2" Stamped D.C. Remon. Witness Corner  
30.00' South.  
Set Carsonite Stake at W.C.

B-5 Accepted above Iron Bar as Best  
Remaining Evidence and replaced same  
with 2 1/2" Stamped D.C. Remon. Corner.  
New Witnesses  
Hemlock 5" S08°W 4.27' Nail/Tag  
Cedar 8" S56°W 22.13' Nail/Tag  
Maple 3" S48°E 16.93' Nail/Tag  
W.Pine 24" S86°E 9.41' Ex. B.T.  
Placed Carsonite Marker 1' South.

Signed by Robert F. Perkins Date Oct. 24, 1998

Surveyor's Michigan License No. 12027

APPROVED BY THE DICKINSON COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT  
345 OF 1990 AT A MEETING HELD ON  
12-7-98

RO Perkins  
COUNTY REPRESENTATIVE

