

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:24

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
<u>Breitung Twp.</u>		
1. Public Land Survey	T <u>40NR 30W</u>	<u>C-2</u>
	T <u>    </u> R <u>    </u>	<u>C-3</u>
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____

REGISTERED OF DEEDS  
 LUCAS COUNTY  
 200 N. HOOPER ST. COLUMBUS, OH 43215

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert F. Perkins, in a field survey on Aug. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	●	5		4		3		2		1	
3		●										
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2 ¼ Corner Common to Sections 6/5 Post by James H. Mullett, D.S. 1849 Original Bearing Trees Aspen 2" S37°W(M.B.) 48 Lk. Aspen 2" N88°W(M.B.) 26 Lk. 8-25-1978 E. Kazianka, RLS 14765 Set Iron Pipe as described in Certificate #191	C-3 Section Corner Common to 5-6-7-8 Post by James H. Mullett, D.S. 1849 Original Bearing Trees Aspen 6" S35°E 69 Lk. Aspen 6" S61°W 39 Lk.
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 No Evidence of Original Corner or its Accessories Found. Found 1" Iron Pipe described in "A" with two 1978 Bearing Trees.	C-3 No Evidence of Original Corner or its Accessories Found. Found 5/8" x 16" Iron Bolt in Centerline Asphalt Road. Removed same and Found 1½" Iron Pipe (Lying on its side) as noted on Old Corner Report #823 by J. Smallwood, RLS dated 4-16-1964.
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 Replaced Found Iron Pipe with 2½" Stamped D.C. Remon. Corner. New Witnesses W.Pine 8" N31°W(M.B.) 3.88' Nail/Tag W.Pine 7" N65°E(M.B.) 23.60' Nail/Tag Spruce 10" S50°E(M.B.) 41.00' Nail/Tag W.Pine 7" S4°W(M.B.) 13.20' Nail/Tag Placed Carsonite Marker 1.0' West Centerline E & LS RR East ±152'	C-3 Remonumented above with 2½" Stamped D.C. Remon. Corner in Monument Box. New Witnesses P.Pole #74-0135 N63°W(M.B.) 50.19' Nail/Tag P.Pole #74-0136 S45°E(M.B.) 55.49' Nail/Tag Oak 3" S34°W(M.B.) 40.50' Nail/Tag Cherry 2" N48°E(M.B.) 45.91' Nail/Tag Placed Carsonite Marker 30.00' North
--	---

Signed by Robert F. Perkins Date Oct. 24, 1998

Surveyor's Michigan License No. 12027  
 APPROVED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-7-98  
RF Perkins

