

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 1998 DEC 14 PM 12:24

For corners in

<u>Dickinson</u>	Located in:	Corner Code #
(County)		
City of Iron Mountain		
1. Public Land Survey	T <u>40NR 30W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 DICKINSON COUNTY
 200 N. MAIN ST. BENTON, MI 49707

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Aug. 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:


C-12 $\frac{1}{2}$ Corner Common to Sections 31-32
 Post by James H. Mullett, D.S. 1849
 Original Bearing Trees
 Birch 6" N32°E 08 Lk.
 Birch 8" N75°W 24 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 No Evidence of Original Corner or Accessories Found.
 Found 5/8" Iron Bar that had been previously set from Points in Plat of Victoria Park Circa 1970.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Accepted above found Iron Bar and replaced same with 3 1/2" Stamped D.C. Remon. Corner buried ± 2" (in Lawn).
 New Witnesses
 N.W. Corner Garage Fdn. S34°W(M.B.) 126.03'
 N.E. Corner Garage Fdn. S23°W(M.B.) 119.02'
 Box Elder 7" N56°W(M.B.) 92.47' Nail/Tag
 Box Elder 5" S25°E(M.B.) 30.81' Nail/Tag
 P.Pole (No #) N12°E (M.B.) 42.80 Nail/Tag



Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027

Date Oct. 24, 1998

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 12-7-98
RD Perkins
 COUNTY REPRESENTATIVE