

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:24

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
<u>Breitung Twp.</u>		
1. Public Land Survey	T <u>40NR 30W</u>	<u>D-7</u>
	T <u> R </u>	<u>E-1</u>
	T <u> R </u>	_____
	T <u> R </u>	_____
2. Property Controlling in Section	S <u> T </u>	_____
	S <u> T </u>	_____
3. Miscellaneous Property in Sec.	S <u> T </u>	_____
	S <u> T </u>	_____

REGISTERED OF DEEDS
 DICKINSON COUNTY
 1998 DEC 14

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
 5. Private Claims _____

I, Robert E. Perkins, in a field survey on Aug. 18, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1				●								
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7				●								
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-7 $\frac{1}{4}$ Corner Common to Sections $\frac{17}{20}$
 Post by James H. Mullett, D.S. 1849
 Original Bearing Trees
 Aspen 4" N14°W 08 Lk.
 Aspen 4" S78°E 09 Lk.

E-1 North Corner Common to sections 4 & 5
 Post by James H. Mullett, D.S. 1849
 Original Bearing Trees
 Aspen 12" S75°E 13 Lk.
 Aspen 12" S20°W 24 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 No Evidence of Original Corner or Accessories found.
 Found 1" Iron Pin referred to by E.C. Muller, P.S. in Certificate #189 dated 8-21-1978.

E-1 No Evidence of Original Corner or Accessories Found.
 Found 1" Iron Pipe with 4" D.N.R. Brass Cap set by B. Buckler, RLS on 7-28-1955 and Filed on Old Corner Report No. 119.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 Placed 2½" Stamped D.C. Remon. Corner at above described Iron Bar.
 New Witnesses:
 Found 1½" Iron Pipe N88°W(M.B.) 16.35'
 1978 BT's Found and Upgraded:
 S. Maple 14" N27°W(M.B.) 9.52' Nail/Tag
 Oak 14" N47°E(M.B.) 17.60' Nail/Tag
 Oak 14" S08°E(M.B.) 25.21' Nail/Tag
 Placed Carsonite Marker 0.6' North of Corner.

E-1 Found Pipe Marker as described in "B" above. Also found one 1955 BT dead.
 New Witnesses:
 Maple 4" S72°W(M.B.) 27.5' Nail/Tag
 Maple 6" N33°W(M.B.) 12.89' Nail/Tag
 Oak 10" N63°E(M.B.) 7.35' Nail/Tag
 Oak 10" S29°E(M.B.) 37.48' Nail/Tag
 Placed Carsonite Marker 1.0' North of Corner.

Signed by Robert E. Perkins Date Oct. 24, 1998

Surveyor's Michigan License No. 12027

STATE OF MICHIGAN
 DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
12-7-98
 PROFESSIONAL SURVEYOR

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1985

Libor 2 Page 397