

**SURVEY &  
REMONUMENTATION**

**MAR 03 1998**

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

1997 DEC 10 PM 3:54

For corners in Dickinson (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

Breitung Twp.

1. Public Land Survey	T <u>40N</u> R <u>30W</u>	<u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	M.C. S. of _____
	T _____ R _____	K-10 _____
2. Property Controlling in Section	S _____ T _____ R _____	#002 _____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS  
DICKINSON COUNTY  
RON MOORE, CLERK

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert F. Perkins, in a field survey on Oct. 28, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-12  $\frac{1}{2}$  Corner Common to Sections 34 and 35  
Post by James H. Mullett, D.S. 1849  
Original Bearing Trees  
Sugar 10" N30°E 07 Lks.  
Sugar 8" S89°W 13 Lks.

NORTH MEANDER CORNER 26/25  
Post by James H. Mullett, D.S. 1849  
Original Bearing Trees  
Aspen 10" N44°E 28 Lks.  
Aspen 6" N21°W 14 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12-9-97

ROW

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:** COUNTY REPRESENTATIVE

I-12 No Evidence of Original Corner or Accessories Found.  
Dickinson Co. Road Comm. Surveyors made a direct Tie to an Iron Pipe at this Location in 1934. (F.B.1934). Iron Pipe was later lost due to Road Construction. Very old Rock and Fence Line run West from Road.


N-M.C. 26/25  
No Evidence of Original Corner or Accessories Found.  
It appears from the Remains of Trees in the Water that the Lake Level was Raised at some time subsequent to the Original Survey, probably by the construction of the Outlet Control Structure. As a result the Original Meander Corners were Lost. Corner Location researched in 1996 Remon. Program.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-12 Set 2  $\frac{1}{2}$ " Stamped D.C. Remon. Corner from found points set on 1934 D.C.R.C. Survey as described in I-12.  
New Witnesses:  
Hemlock 10" N74°W(M.B.) 102.38' Nail/Tag  
Lynn 5" S46°W(M.B.) 76.73' Nail/Tag  
N. Post G. Rail N05°W(M.B.) 38.71' Nail/Tag  
S. Post G. Rail S06°E(M.B.) 198.06' Nail/Tag  
Centerline Road 18.5' West  
Corner falls under Guard Rail

N-M.C. 26/25  
Set 2  $\frac{1}{2}$ " Stamped D.C. Remon Corner 1013.15 feet Due south  $\frac{1}{2}$  Corner 26/25 North of High Water Mark  $\pm 10'$   
New Witnesses:  
Cedar 4" N37°W (M.B.) 11.42' Nail/Tag  
Cedar 3" N87°W(M.B.) 10.95' Nail/Tag  
Cedar 5" N44°E(M.B.) 10.50' Nail/Tag  
Cedar 3" S48°E(M.B.) 9.15' Nail/Tag

Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027



Date Nov. 26, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN., 1983