

MAY 07 1997

RECORDED

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1996 DEC 18 AM 11:16

For corners in DICKINSON (County) Located In: Corner Code # BREITUNG TWP. 1. Public Land Survey T 40N R 30W K-6 2. Property Controlling in Section S T R 3. Miscellaneous Property in Section S T R 4. Lot No. , Recorded Plat 5. Private Claims

REGISTER OF DEEDS DICKINSON COUNTY IRON MOUNTAIN, MI 49801

42

Register of Deeds Stamp & File Number

I, ROBERT F. PERKINS, in a field survey on 11-11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column J and row 6.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6 1/4 CORNER COMMON TO SECTIONS 14/13 POST BY J. H. MULLETT 1849 ORIGINAL BEARING TREES BIRCH 6" S79°E 09 L. BIRCH 6" S49°W 07 L.

ACCEPTED BY THE DICKINSON COUNTY SURVEYORS GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 74 OF 1970 AT A MEETING HELD

12-17-96 RFP


COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 CORNER FALLS IN COUNTY ROAD. NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES FOUND. FOUND 5/8" SOLID IRON BAR BURIED 8" IN COUNTY ROAD ± 4' WEST OF CENTERLINE WITH ANCIENT FENCE LINES RUNNING EAST AND WEST FROM CORNER. CORNER ACCEPTED ON NUMEROUS SURVEYS IN AREA.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 ACCEPTED ABOVE DESCRIBED IRON BAR AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET 3 1/2" STAMPED D.C. REMON. WITNESS CORNER 30.00' EAST OF CORNER. NEW WITNESSES: HOUSE CORNER N69°E (M.B.) 77.75' DBL. MAPLE 10" S49°E (M.B.) 66.46' NAIL/TAG LYNN 6" S65°W (M.B.) 50.75' NAIL/TAG + CUT ON S. END 4' BOULDER N12°W (M.B.) 97.51' PLACED CARSONITE MARKER AT W.C.



Signed by [Signature] Date NOVEMBER 6, 1996

Surveyor's Michigan License No. 12027 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983