

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
1997 DEC 10 PM 3:54

For corners in Dickinson (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Breitung Twp.

1. Public Land Survey	T	<u>40N</u>	R	<u>30W</u>	<u>K-9</u>
	T	_____	R	_____	<u>K-10</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

REGISTER OF DEEDS  
DICKINSON COUNTY  
RON MOULTON, CLERK

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	8	5	4	3	2	1					
3											
4	7	6	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Robert F. Perkins, in a field survey on Oct. 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9	Corner Common to Sections 23-24-25-26 Post by James H. Mullett, D.S. 1849 Original Bearing Trees: Blk. Oak 12" N15°E 16 Lks. Aspen 12" S20°W 21 Lks.	K-10	¼ Corner Common to Sections 26/25 Post by James H. Mullett, D.S. 1849 Original Bearing Trees: Sugar 10" S70°E 13 Lks. Birch 10" N12°W 14 Lks.
-----	--	------	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9	No Evidence of Original Corner or Accessories Found. Found 1" Boat Spike projecting ± 2" out of Ground. Also 2 Existing Scribed Witness Trees (Not Original). Corner is 2654.88' East of ½ Corner <u>23</u> and 2624.73' <u>26</u> North ½ Corner Sec. 25/26. Corner Location Researched in 1996 Program.	K-10	No Evidence of Original Corner or Accessories Found. Corner Researched in 1996 Program.
-----	---	------	--

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12-9-97  
ROR  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9	Accepted above Described Boat Spike as Best Available Evidence of Corner. New Witnesses: Maple 3" N19°E(M.B.) 23.80' Nail/Tag Maple 4" S84°W(M.B.) 4.35' Nail/Tag Maple 12" S71°E(M.B.) 11.57' Nail/Tag(Ex.BT) Maple 14" S30°W(M.B.) 11.30' Nail/Tag Carsonite Marker South 0.5' Set 2½" Stamped D.C. Remon. Corner in place of above Described Boat Spike	K-10	Established Corner 2624.75 feet Due South of Section Corner at Point that is 905 feet North of the Center-line of the Former E.I.M. & W. RR as indicated on Railroad R.O.W. Map dated 1892. Set 2½" Stamped D.C. Remon. Corner at above Location. New Witnesses: Oak 16" S73°W(M.B.) 19.26' Nail/Tag Oak 8" S45°E(M.B.) 19.54' Nail/Tag Sugar 8" N75°E(M.B.) 8.92' Nail/Tag Sugar 8" N59°W(M.B.) 30.35' Nail/Tag Carsonite Marker North 1.0'
-----	---	------	--

Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027

