

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 X W.	#K-5
2. PROPERTY CONTROLLING IN SECTION	11, T. 40 N. R. 30 X W.	#14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-5 (Section Corner 11, 12, 13, & 14, T40N, R30W):

- Wood post (Not found. Found 3/4" solid round iron rod in place.)
- Sugar 10 S 4W 25 (Not found. Found 5/8" iron pin S44°40.1'W 168.60 ft.)
- Sugar 14 N35E 9 (Not found. Found 5/8" iron pin S48°57.0'E 177.26 ft.)

Corner 14 (South 1/16 corner between Sections 11 & 12, T40N, R30W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-5: On 6-5-79 found corner as recovered and perpetuated by R. F. Perkins, L. S. #12027, reportedly from information contained in the field books of W. C. Johnson, former Dickinson Co. road engineer. Corner is in an actively-cultivated farm field, with top of monument about 1.2 feet below the ground surface, and perhaps set in concrete. Position agrees substantially with river crossing to W.

Corner 14: Established 7-26-79, from a traverse line, on line between Sec. Cor. 20.308 ch. S and 1/4 cor. 20.308 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-5: 3/4" solid round iron rod, as found or set by Perkins.
5/8" iron pin S44°40.1'W (true) 168.60 ft.
5/8" iron pin S48°57.0'E (true) 177.26 ft.

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
No suitable witness objects nearby.
Declination 3° 05' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE _____

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

