

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 40 N. R. 30 <input checked="" type="checkbox"/> W.	#L-5
2. PROPERTY CONTROLLING IN SECTION <u>12</u>	T. 40 N. R. 30 <input checked="" type="checkbox"/> W.	#16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**Corner L-5 (1/4 section corner between Sections 12 & 13, T40N, R30W):**  
 Wood post (Not found. Found 1" x 28" iron pipe in place.)  
 Hemlock 6 S70E 6 (Not found. No subsequent accessories found.)  
 Maple 16 N53W 23 (Not found. No subsequent accessories found.)

**Corner 16 (East 1/16 corner between Sections 12 & 13, T40N, R30W):**  
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**Corner L-5:** On 6-5-79 replaced the found mon. with new monument described below.  
 Local resident reports pipe to have been there for "a very long time," and that it may have been placed there by W. C. Johnson, former Dickinson Co. road engineer, in the 1930's or 1940's. Corner bears S89°22.7'E 40.023 ch. (record is 40.065 ch.) from Sec. Cor. of similar history and S89°55.0'W 41.186 ch. (record 40.065 ch.) from the Sec. Cor. on range line to E. Corner is 8.00 ch. W of foot of hill, as per original field notes.

**Corner 16:** Established 6-7-79 on line between Sec. Cor. 20.593 ch. E and 1/4 cor. 20.593 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**Corner L-5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 White Pine 10 N69-1/2°E (mag.) 135.3 ft. "1/4S, NBT"  
 SE'ly cor. of concrete irrigation pipe pivot pad N46°W (mag.) 99.6 ft.

**Corner 16:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 6 N77°W (mag.) 9.2 ft. "1/16S, BT"  
 Red Maple 6 N78°E (mag.) 30.2 ft. "1/16S, BT"  
 Declination 2° 20' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 4, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

