

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 40 N. R. 30 <input checked="" type="checkbox"/> W.	#K-2
2. PROPERTY CONTROLLING IN SECTION 1.....	T. 40 N. R. 30 <input checked="" type="checkbox"/> W.	#3 & 3a
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 25, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K-2 (1/4 corner between Sections 1 & 2, T40N, R30W):
 - Wood post (Not found. No subsequent monuments found.)
 - B. Oak 4 N15W 11 (Not found. No subsequent accessories found.)
 - Spruce 6 N83E 6 (Not found. No subsequent accessories found.)
 - Corner 3 (North 1/16 corner between Sections 1 & 2, T40N, R30W) and
 - Corner 3a (Southwest Corner of Lot 4, Section 1, T40N, R30W):
 - Neither of these 2 corners established in original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner K-2: Restored proportionately on line between Sec. Cor. 40.3445 ch. S and True Closing Sec. Cor. bet. Sec. 1 & 2 on 4th Correction Line 51.4395 ch. N. Distance S to stream is 4.73 ch. and N to another stream is 22.87 ch., compared to 4.00 ch. and 23.20 ch. record distance, respectively, but checks perfectly with ridge 1.00 ch. to N
 - Corner 3: Established on line between 1/4 cor. 20.1725 ch. S and SW cor. of Lot 4, Sec. 1 20.1725 ch. N.
 - Corner 3a: Established proportionately on line between Sec. Cor. 80.689 ch. S and True Closing Sec. Cor. bet. Secs. 1 & 2 on 4th Corr. Line 11.095 ch. N.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 - Witnesses for Corner K-2: Red Maple 8 N75°W (mag.) 37.2 ft. "1/4S, NBT"
 - Declination 2° 05' West. Red Maple 10 S46°E (mag.) 20.9 ft. "1/4S, NBT"
 - Witnesses for Corner 3: Red Maple 6 S33°E (mag.) 24.7 ft. "1/16S, BT"
 - Declination 1° 45' West. Red Maple 3 N76°E (mag.) 19.7 ft. "1/16S, BT"
 - Witnesses for Corner 3a: Red Maple 10 N77°W (mag.) 9.1 ft. "Lot 1, BT"
 - Declination 2° 40' West. Red Maple 4 S 5°E (mag.) 38.3 ft. "NWNW, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

DATE March 8, 1988



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581