

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 <del>X.</del> W.	#H-3
2. PROPERTY CONTROLLING IN SECTION	3, T. 40 N. R. 30 <del>X.</del> W.	#16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 12, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner H-3 (1/4 corner between Sections 3 & 10, T40N, R30W):**

- Wood post (Not found. No subsequent monuments found.)
- Birch 6 N55E 6 (Not found. No subsequent accessories found.)
- Aspen 3 S45E 2 (Not found. No subsequent accessories found.)

**Corner 16 (East 1/16 corner between Sections 3 & 10, T40N, R30W):**

Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner H-3:** Restored on line between Sec. Cor. 36.525 ch. W and Sec. Cor. 39.980 ch. E. There was found to be a probably shortage of 3.455 ch. in this sec. line as compared to the original field notes, and comparing distances to natural objects recorded in the field notes, most or all of it occurs in the West 1/2 mile. The same type of discrepancy, although not of the same magnitude, was noted on the south side of Sec. 10.

**Corner 16:** Established on line between Sec. Cor. 19.990 ch. E and 1/4 cor. 19.990 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner H-3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 4 S60°W (mag.) 16.1 ft. "1/4S, NBT"  
 Red Maple 4 S79°E (mag.) 31.6 ft. "1/4S, NBT"  
 Declination 3° 10' West.

**Corner 16:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 J. Pine 8 S 4°W (mag.) 32.7 ft. "1/16S, BT"  
 J. Pine 9 N18°W (mag.) 51.6 ft. "1/16S, BT"  
 Declination 2° 25' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

