

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 W.	#H-5 & I-4
2. PROPERTY CONTROLLING IN SECTION	10 T. 40 N. R. 30 W.	#16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner H-5 (1/4 cor. between Sections 10 & 15, T40N, R30W):**
 Wood post (Not found. No subsequent monuments found.)
 Tamarack 3 N19W 13 (Not found. No subsequent accessories found.)
 Tamarack 3 S37W 14 (Not found. No subsequent accessories found.)
Corner I-4 (1/4 corner between Sections 10 & 11, T40N, R30W):
 Wood post (Not found. No subsequent monuments found.)
 Hemlock 10 S78W 22 (Not found. No subsequent accessories found.)
 Birch 4 N25E 11 (Not found. No subsequent accessories found.)
Corner 16 (East 1/16 corner between Sections 10 & 15, T40N, R30W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H-5: Restored 7-13-79 in an old N & S fence line, traditionally the N & S 1/4 lines of Secs. 10 & 15 as evidenced by old field edges, and on line bet. Sec. Cors. 37.161 ch. W and 40.547 ch. E. Corner falls in old junk pile, of the type farmers formerly used to pile around fence corners and on fence lines. Corner is about 3.50 ch. W of stream, although field notes say it should be about 5.05 ch. There are measurement blunders in the original survey measure of this sec. line. **Corner I-4:** Restored 7-11-79 on line between Sec. Cors. 40.445 ch. to N and to S. **Corner 16:** Established 7-16-79 on line between Sec. Cor. 20.274 ch. E and 1/4 cor. 20.274 ch. W. Fence corner N22°03'W 56.36 ft., but could not see any good evidence for putting it there.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Witnesses for Corner H-5: Tamarack 11 N20°W (mag.) 184.0 ft. "1/4S, NBT"
 Declination 6° 10' West. Tamarack 8 N89°W (mag.) 91.9 ft. "1/4S, NBT"
 Witnesses for Corner I-4: Red Maple 8 N32-1/2°E (mag.) 42.1 ft. "1/4S, NBT"
 Declination 2° 20' West. Red Maple 5 S27° E (mag.) 11.6 ft. "1/4S, NBT"
 Witnesses for Corner 16: Red Maple 6 S18° W (mag.) 9.3 ft. "1/16S, BT"
 Declination 6° 20' West. Jack Pine 8 N26° E (mag.) 40.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

DATE March 7, 1980

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

