

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#L-3
2. PROPERTY CONTROLLING IN SECTION	1, T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#15 & 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 31, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner L-3 (1/4 corner between Sections 1 & 12, T40N, R30W):
 Wood post (Not found. No subsequent monuments found.)
 W. Pine 4 N28W 13 (Not found. No subsequent accessories found.)
 Sugar 4 S34E 20 (Not found. No subsequent accessories found.)
Corner 15 (West 1/16 corner between Sections 1 & 12, T40N, R30W) and
Corner 16 (East 1/16 corner between Sections 1 & 12, T40N, R30W):
 Neither of these 2 corners set in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner L-3: Restored on line between original sec. cor. 40.388 ch. E and original sec. cor. 40.388 ch. W.
Corner 15: Established on line between Sec. Cor. 20.194 ch. W and 1/4 cor. 20.194 ch. E. Falls on side of north-facing slope of a high granite knob.
Corner 16: Established on line between Sec. Cor. 20.194 ch. E and 1/4 cor. 20.194 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner L-3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Pine 12 N70°W (mag.) 14.6 ft. "1/4S, NBT"
 Red Oak 20 S62°W (mag.) 23.5 ft. "1/4S, NBT"
 Declination 4° 50' West.
Corner 15: ⊕ chiselled on rock outcrop, with a small stone cairn over it.
 W. Pine 15 N24°E (mag.) 12.6 ft. "1/16S, BT"
 Cedar 6 S64°E (mag.) 11.0 ft. "1/16S, BT" Distances horizontal.
 Cedar 4 S84°W (mag.) 13.8 ft. "1/16S, BT" Declination 3° 20' West.
Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Oak 5 N11°W (mag.) 10.0 ft. "1/16S, BT"
 Red Oak 5 S19°E (mag.) 21.0 ft. "1/16S, BT" Declination 5° 00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 APPROVED AND SIGNED BY Arthur O. Enger DATE March 4, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

MICHIGAN Department of Natural Resources
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

