

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY. | T. 40 N. R. 30 W. <input checked="" type="checkbox"/> | #J-5 |
| 2. PROPERTY CONTROLLING IN SECTION <u>11</u> | T. 40 N. R. 30 W. <input checked="" type="checkbox"/> | #15 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ S. R. _____ E. W. _____ | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 11, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J-5 (1/4 corner between Sections 11 & 14, T40N, R30W):
 Wood post (Not found. No subsequent monuments found.)
 Hemlock 8 N15W 13 (Not found. No subsequent accessories found.)
 Hemlock 8 S60E 17 (Not found. No subsequent accessories found.)

Corner 15 (West 1/16 corner between Sections 11 & 14, T40N, R30W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J-5: Restored between Sec. Cor. S88°48'W 39.505 ch. and Sec. Cor. S88°21'E 39.7535 ch. This position was determined to be about the most probable traditional location of the corner by conforming its restoration to observed old fence lines and fence corners presumed to be on interior farm subdivision lines and at old farm subdivision corners of Sec. 14, which date back to the late 19th or early 20th centuries. There appears to be no way in which a straight line between Sections 11 & 14 can be made to conform to landmarks noted in the original field notes for the line, supporting the suspicion that it probably was not run very accurately in the original survey. **Corner 15:** Established on line between Sec. Cor. S88°48'W 19.7525 ch. and 1/4 cor. N88°48' E 19.7525 ch. Found a 1" I.D. iron pipe, extending 4-1/2 ft. above ground, N24°18'E 101.6 ft., set by loggers for an approx. corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J-5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Hemlock 5 N18°W (mag.) 7.8 ft. "1/4S, NBT"
 Cedar 5 S89°W (mag.) 31.8 ft. "1/4S, NBT"
 Declination 4° 30' West. Note: Monument leans to N because of large buried rock beneath. Punch mark on cap is over the true point.

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 5 S45°E (mag.) 25.3 ft. "1/16S, BT"
 Red Maple 9 N60°E (mag.) 32.8 ft. "1/16S, BT"
 Declination 2° 55' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE _____

CHIEF OF SURVEY PARTY
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

