

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ S. _____ R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION	2, T. 40' N. <input checked="" type="checkbox"/> S. R. 30 <input checked="" type="checkbox"/> W.	#3
3. MISCELLANEOUS PROPERTY IN SECTION	2, T. 40' N. <input checked="" type="checkbox"/> S. R. 30 <input checked="" type="checkbox"/> W.	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 23, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on July 25, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 3 (North 1/16 corner between Sections 2 & 3, T40N, R30W):
 Not established in original survey nor subsequently, apparently.
Miscellaneous Property Corner: Midpoint of West line of NW1/4 NW1/4, Sec. 2, T40N, R30W.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 3: Established 8-23-79 proportionately on line between 1/4 cor. 20.1055 ch. S and True Closing Corner on 4th Correction Line between Sections 2 & 3, 31.163 ch. N. Corner, like that at the 1/4 corner between Secs. 2 & 3, falls in a large actively-cultivated farm field.
Miscellaneous Property Corner: Established 7-25-79 on line between a monument at the SW corner of Lot 4, Sec. 2, 40-30 10.0525 ch. N and a monument at the N1/16 cor. bet. Sec. 2 & 3, 40-30 10.0525 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 3: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap.
 1. D.N.R. mon. at 1/4 bet. 2 & 3, S1°32.3'W (true) 1326.95 ft.
 2. Squared cedar post, N1°32.3'E (true) 663.47 ft.
 Declination 2° 35' West.
Miscellaneous Property Corner: 4" x 4" x 5' squared & scribed cedar post.
 1. Red Pine 6 S64°W (mag.) 27.9 ft. "S3, BT"
 2. Red Pine 8 N76°E (mag.) 75.2 ft. "S2, BT"
 Declination 2° 00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 07, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

