

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#L-1
2. PROPERTY CONTROLLING IN SECTION	1, T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#1
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner L-1 (North 1/4 corner of Section 1, T40N, R30W) and  
Corner 1 (West 1/16 corner on North Side of Section 1, T40N, R30W):  
Neither corner established in original survey nor subsequently, apparently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner L-1: Established 8-29-79 on 4th Correction Line proportionately on line between monuments at Standard 1/4 cor. on South side of Sec. 32, 41-29 24.541 ch. W and Standard Sec. Cor. at SE cor. of Sec. 32, 41-29 15.566 ch. E. Corner thus set is 39.9385 ch. from closing section corners to E and to W.**

**Corner 1: Established 8-28-79 on 4th Correction Line, proportionately on line between monuments at Std. 1/4 cor. on S side of Sec. 32, 41-29 4.572 ch. W and Std. Sec. Cor. at SE cor. of Sec. 32, 41-29 35.5355 ch. E.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner L-1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
Red Oak 12 N271/2°E (mag.) 22.3 ft. "1/4S, BT"  
Red Maple 4 N71° W (mag.) 18.2 ft. "1/4S, BT"  
Declination 3°25' West.**

**Corner 1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
Red Maple 10 S72°W (mag.) 5.5 ft. "1/16S, BT"  
Red Maple 6 S80°E (mag.) 12.2 ft. "1/16S, BT"  
Declination 4°15' West.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

