

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 ^{N.} X. R. 30 ^{X.} W.	#K-1
2. PROPERTY CONTROLLING IN SECTION	2 T. 40 ^{N.} X. R. 30 ^{X.} W.	#2
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 27, 19 79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-1 (Closing Corner on 4th Correction Line between Sections 1 & 2, T40N, R30W):
 Wood post (Not found. Found approx. corner post.)
 Hemlock 10 S80E 7 (Not found. No subsequent accessories found.)
 Hemlock 10 S27W 13 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner on North Side of Section 2, T40N, R30W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-1: Restored on 4th Correction Line on line between monuments at Standard Sec. Cor. at SW cor. of Sec. 32, 41-29 24.338 ch. W and at Standard 1/4 cor. on South side of Sec. 32, 41-29 15.397 ch. E. Found a 4" x 4" x 4' squared cedar post about 15-20 yrs. old, set by foresters for an approx. cor., N82°W 9.3 ft.

Corner 2: Established on 4th Correction Line, proportionately on line between monuments at Std. Sec. Cor. at SW cor. of Sec. 32, 41-29 4.219 ch. W and at Std. 1/4 cor. on S side of Sec. 32, 41-29 35.516 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 6 S 4°W (mag.) 16.5 ft. "S 2, NBT"
 Red Maple 4 N 3°W (mag.) 23.5 ft. "S32, NBT"
 Red Maple 5 N55°E (mag.) 21.6 ft. "S32, NBT"
 Distances horizontal. Declination 3° 25' West.

Corner 2: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap, set in rock mound.
 Red Pine 7 S72°E (mag.) 27.0 ft. "1/16S, BT"
 Red Pine 7 S35°W (mag.) 35.2 ft. "1/16S, BT"
 Declination 3° 15' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

