

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	(DICKINSON COUNTY) LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#J-1
2. PROPERTY CONTROLLING IN SECTION 2.....	T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#1
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. W. <input type="checkbox"/>	
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J-1 (North 1/4 corner of Section 2, T40N, R30W) and

Corner 1 (West 1/16 corner on North Side of Section 2, T40N, R30W):
Neither corner established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J-1: Established 8-1-79 on 4th Correction Line on line between monuments at South 1/4 cor. of Sec. 31, 41-29 24.0395 ch. W and at SE cor. of Sec. 31, 41-29 15.900 ch. E. Corner thus set is 40.2375 ch. from closing section corners to E and to W.

Corner 1: Established 7-30-79 on 4th Correction Line on line between monuments at South 1/4 cor. of Sec. 31, 41-29 3.9205 ch. W and at SE cor. of Sec. 31, 41-29 36.0185 ch. E. Corner thus set is 20.119 ch. W of 1/4 cor. on N side of Sec. 2 and 20.119 ch. E of closing sec. cor. bet. Sec. 2 & 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J-1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Black Ash 4 S30°E (mag.) 17.1 ft. "1/4S, BT"
Cedar 12 S 7°W (mag.) 48.2 ft. "1/4S, BT"
Declination 2° 45' West.

Corner 1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Sugar Maple 8 S76°E (mag.) 21.0 ft. "1/16S, BT"
Sugar Maple 8 N69 1/2°E (mag.) 23.2 ft. "1/16S, BT"
Declination 1° 20' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

