

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(DICKINSON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 ^N _S , R. 30 ^W _E	#I-1
2. PROPERTY CONTROLLING IN SECTION	T. 40 ^N _S , R. 30 ^W _E	#3b
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____, R. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I-1 (Closing Corner on 4th Correction Line between Sections 2 & 3, T40N, R30W):

Wood post (Not found. Found DNR monument by B. D. Buckler.)
 Alder 3 S63E 24 (Found Elm 18 N31°W 126 lks., by Buckler.)
 Alder 3 S10W 25 (Found Elm 24 S58°W 148 lks., by Buckler.)

Corner 3b (Southwest Corner of Lot 4, Section 2, T40N, R30W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-1: On 7-27-55, B. D. Buckler, R.L.S., set a monument to represent this corner "by proportionate measure in three directions, west to line tree, ledge, and Sec. Cor., east and south to stream. No evidence of original corner. "I determined that the monument as set did not close on the Correction Line, so on 8-22-79 moved it N1°31'E 11.47 ft. to a new position that does close on it. I feel that this is where Buckler should have placed it in 1955. There is still about the same degree of agreement with the features used by Buckler to establish his corner.

Corner 3b: Established 7-25-79 proportionately on line bet. Sec. Cor. 80.421 ch. S and True Closing Corner on 4th Corr. Line bet. Secs. 2 & 3, 11.058 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-1: 1" I.D. x 42" iron pipe with 4" brass cap.
 Balm-of-Gilead 7 S24°W (mag.) 21.5 ft. "S3, NBT"
 Balm-of-Gilead 10 S15°E (mag.) 23.9 ft. "S2, NBT"
 Note: Buckler's NBT's are both dead and down. Declination is 2° 20' West.

Corner 3b: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Balm-of-Gilead 5 N38°W (mag.) 21.9 ft. "L1, S3, BT"
 Balm-of-Gilead 5 N47°E (mag.) 28.9 ft. "L4, S2, BT"
 Declination 2° 55' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

