

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	(DICKINSON COUNTY) LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 W.	#I-2
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	3 T. 40 N. R. 30 W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 22, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on August 24, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and or subsequent restoration:

Corner I-2 (1/4 corner between Sections 2 & 3, T40N, R30W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 14 N40E 16 (Not found. No subsequent accessories found.)
 Sugar 12 S58W 13 (Not found. No subsequent accessories found.)

Miscellaneous Property Corner: Midpoint of South line of SE1/4 NE1/4, Sec. 3, T40N, R30W.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-2: Restored 8-22-79 proportionately on line bet. Sec. Cor. 40.2105 ch. S and true closing sec. cor. on 4th Correction Line between Secs. 2 & 3, 51.2685 ch. N.

Miscellaneous Property Corner: Established 8-24-79 on computed E & W 1/4 line of Sec. 3, S89°41'30"W 659.15 ft. from a monument set at 1/4 cor. bet. Sec. 2 & 3. Monument purports to mark the midpoint of the line between the SE NE 3 and NE SE 3, as computed from measurements around the perimeter of Sec. 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-2: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap; top of mon. is about one (1) foot below ground surface.

1. DNR mon. at S1/16 bet. 2 & 3, S1°32.3'W 1326.95 ft.
2. DNR mon. at N1/16 bet. 2 & 3, N1°32.3'E 1326.95 ft.
3. DNR mon. at property cor. on E & W 1/4 line of Sec. 3, S89°37.2'W 659.15 ft.
4. 6" cedar post with DNR location tag, N88°34'W 681.4 ft.

Miscellaneous Property Corner: 1" I.D. x 18" iron pipe with 3 3/4" aluminum cap; top of monument is about 1 foot below ground surface.

1. Nail with brass ref. tag, in 6" cedar post N45°23'W 30.55 ft.
2. Nail with brass ref. tag, in 6" cedar post S44°37'W 30.48 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581