

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	(DICKINSON COUNTY) LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 <input checked="" type="checkbox"/> W.	#1-3
2. PROPERTY CONTROLLING IN SECTION	2 T. 40 N. R. 30 <input checked="" type="checkbox"/> W.	#10
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I-3 (Section Corner 2, 3, 10, & 11, T40N, R30W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Hemlock 12 N37E 7 (Not found. No subsequent accessories found.)  
 Elm 10 N17W 14 (Not found. No subsequent accessories found.)

**Corner 10 (South 1/16 corner between Sections 2 & 3, T40N, R30W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I-3:** Restored 7-12-79 at record distance of 79.960 ch. from an original sec. cor. to E, and by reference to swamp edge to S and stream crossing to N. Corner thus set also agrees with swamp edge and foot of hill to W and with a stream crossing to E. There appears to be errors in the original survey measure of the mile going W from this corner, but not in the mile going E; thus proportionate measurements E & W did not seem appropriate.

**Corner 10:** Established 7-24-79 on line between Sec. Cor. 20.105 ch. S and 1/4 cor. 20.105 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner I-3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Aspen 6 N75°E (mag.) 11.8 ft. "S2, NBT"  
 Aspen 8 N45°W (mag.) 17.1 ft. "S3, NBT"  
 Aspen 6 S24°W (mag.) 17.5 ft. "S10, NBT"

**Corner 10:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Cedar 9 S26°E (mag.) 14.6 ft. "1/16S, BT"  
 Cedar 9 N33°W (mag.) 7.3 ft. "1/16S, BT"  
 Declination 2°30' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

