

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 K.	#H-1
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	T. 40 N. R. 30 K.	#2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 21, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H-1 (North 1/4 corner of Section 3, T40N, R30W) and
Corner 2 (East 1/16 corner on North Side of Section 3, T40N, R30W):
 Neither corner established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H-1: Established on 4th Correction Line on line between monuments at Standard 1/4 cor. on South side of Section 36, 41-30 25.654 ch. West and Standard Township Corner bet. Sec. 31, 41-29 and Sec. 36, 41-30 14.292 ch. East. Corner thus set is 39.911 ch. from closing sec. corners to E and to W.
Corner 2: Established on 4th Correction Line on line between monuments at Standard Township Corner bet. Sec. 31, 41-29 and Sec. 36, 41-30 5.664 ch. West and Standard 1/4 cor. on South side of Sec. 31, 41-29 36.154 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H-1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 5 S68°W (mag.) 34.7 ft. "1/4S, BT"
 Red Maple 5 S25°E (mag.) 16.4 ft. "1/4S, BT"
 Declination 5°50' West.

Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Black Ash 6 N83°E (mag.) 33.3 ft. "1/16S, BT"
 Black Ash 4 S51°E (mag.) 33.0 ft. "1/16S, BT"
 Declination 3°25' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 27, 1980

MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

