

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*Dickinson*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>40</u> <del>N.</del> <del>R.</del> <u>30</u> <del>W.</del>	G2
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>40</u> <del>N.</del> <del>R.</del> <u>30</u> <del>W.</del>	14 & 14a
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G2 (1/4 corner between Sections 3 & 4, T40N, R30W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Hemlock 16 N50W 17 ( " " " " " " )  
 Sugar 10 N34E 11 ( " " " " " " )

**Corner 14 (North 1/16 corner between Sections 3 & 4, T40N, R30W) and  
 Corner 14a (Southeast Corner of Lot 1, Section 4, T40N, R30W):**

Neither of these corners established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G2:** Re-established 6/13/75 proportionately on line between Sec. Cor. 3398.2 ft. N and 2665.8 ft. S.  
**Corner 14:** Established 4/19/76 proportionately on line between 1/4 cor. 1312.9 ft. S and Sec. Cor. 2086.0 ft. N.  
**Corner 14a:** Established 4/19/76 proportionately on line between 1/4 cor. 2625.8 ft. S and Sec. Cor. 773.1 ft. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G2:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
 Jack Pine 6 S31 1/2 E (mag.) 20.8 ft. "1/4S, NBT"  
 White Pine 12 N72° E (mag.) 15.9 ft. "1/4S, NBT"  
**Corner 14:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 6 N 4°E (mag.) 10.1 ft. "1/16S, BT"  
 Red Oak 8 S74°E (mag.) 14.3 ft. "1/16S, BT"  
**Corner 14a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Oak 10 (West of twins) S7°W (mag.) 39.3 ft. "NENE, BT"  
 Red Maple 4 N21°W (mag.) 31.0 ft. "Lot 1, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE December 21, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

