

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. 40 N. XX R. 30 XX W.	E2	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION _____	4, T. 40 N. XX R. 30 XX W.	3 & 3a	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E2 (1/4 corner between Sections 4 & 5, T40N, R30W):

Wood post (Not found. Found 1 1/2" I.D. x 36" iron pipe in place.)
 Aspen 4 N81W 19 (Not found. Found R. F. Perkins' NBT.)
 Aspen 5 N 7E 11 (Not found. Found R. F. Perkins' NBT.)

Corner 3 (North 1/16 corner between Sections 4 & 5, T40N, R30W):

Corner 3a (Southwest Corner of Lot 4, Section 4, T40N, R30W):

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E2: On 6/16/75 replaced the found monument with a new monument described below. Iron pipe reported to have been set by Co. Rd. Commission surveyor in 1934, but how set is not known. Corner bears N1°18'00" E 2627.9 ft. from a similar pipe at SW sec. cor. and S1°21'10"E 3610.6 ft. from NW sec. cor. Such a bend in the sec. line seems unlikely even in the original subdivision survey; however, the corner has been too much used by local surveys as is to warrant changing it.
Corner 3: Established 4/16/76 proportionately on line between 1/4 cor. 1386.9 ft. S and closing Sec. Cor. 2224.5 ft. N. Found an old, down barbed-wire fence running E & W 13.5 ft. N of corner, but no evidence of a corner.
Corner 3a: Established 4/16/76 proportionately on line between 1/4 cor. 2773.7 ft. S and closing Sec. Cor. 837.7 ft. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E2: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 W. Pine 10 S42 1/2°E (mag.) 30.9 ft. "1/4S, NBT"
 R. Oak 13 S73°W (mag.) 30.7 ft. "1/4S, NBT" By Perkins

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Oak 10 N26°E (mag.) 19.9 ft. "1/16S, BT"
 Red Oak 7 S57°E (mag.) 15.2 ft. "1/16S, BT"

Corner 3a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 4 S38°E (mag.) 67.7 ft. "NWNW, BT"
 Aspen 7 N70°E (mag.) 33.3 ft. "Lot 4, BT"

Variation 1°35' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 27, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581