

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>4</u> , T. <u>40</u>	N. _____ E. _____ S., R. <u>30</u> W. _____	<u>8, 11, & 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 16, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 8 (West 1/16 corner on E & W 1/4 line of Section 4, T40N, R30W):

Corner 11 (Center of SW $\frac{1}{4}$ of Section 4, T40N, R30W):

Corner 15 (West 1/16 corner between Sections 4 & 9, T40N, R30W):
None of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 8: Established on line between W $\frac{1}{4}$ corner 1289.1 ft. W and Center 1/4 corner 1289.1 ft. E.

Corner 11: Established at intersection of quarter-quarter section lines.

Corner 15: Established on line between Sec. Cor. 1327.45 ft. W and 1/4 corner 1327.45 ft. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 $\frac{1}{2}$ " aluminum cap and 1/2" x 12" re-inforcing rod welded to bottom end.

Witnesses for Corner 8: Red Oak 7 N 3 $^{\circ}$ E (mag.) 23.7 ft. "1/16S, BT"

Red Oak 6 N79 $^{\circ}$ W (mag.) 19.9 ft. "1/16S, BT"

Witnesses for Corner 11: Red Maple 4 S29 $^{\circ}$ W (mag.) 24.2 ft. "1/16S, BT"

(Distances horizontal) Red Maple 3 S29 $^{\circ}$ E (mag.) 22.8 ft. "1/16S, BT"

Witnesses for Corner 15: Red Pine 16 S54 $^{\circ}$ E (mag.) 20.9 ft. "1/16S, BT"

White Pine 16 S41 $^{\circ}$ W (mag.) 19.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 18, 1976

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources
13581

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

