

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 40 N. R. 30 E. W.	F2 & F3
2. PROPERTY CONTROLLING IN SECTION 4	T. 40 N. R. 30 E. W.	12
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F3 (1/4 corner between Sections 4 & 9, T40N, R30W):
 Wood Post (Not found. See B for monument found.)
 Aspen 4 S15E 16 (" " No subsequent accessories found.)
 Aspen 4 N51W 14 (" " " " " ")

Corner F2 (Center of Section 4, T40N, R30W):
Corner 12 (South 1/16 corner on N & S 1/4 line of Section 4, T40N, R30W):
 Neither of these corners established in original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F3: Re-established 6/17/75 on line between Sec. Cor. 2654.9 ft. to E and to W. Found a 1" I.D. x 36" iron pipe with 4" aluminum cap set by E. Kazianka of Kimberlands, Ltd., stamped "Approx. Corner, 1/4 ⁴/₉" and dated 9-18-64, S35°15.5'E 61.80 ft. from corner herein established. A personal conversation with Mr. Kazianka confirmed this monument as only approximating the corner represented.

Corner F2: Established 6/13/75 at intersection of quarter-section lines.
Corner 12: Established 6/16/75 on line between S ¹/₄ corner 1322.55 ft. S and Center ¹/₄ corner 1322.55 ft. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 ¹/₂" aluminum cap and ¹/₂" x 12" re-inforcing rod welded to bottom end.

Witnesses for Corner F3: W. Pine 8 N56°W (mag.) 30.4 ft. "1/4S, NBT"
 (Variation 1°35' West) W. Pine 10 N51°E (mag.) 28.9 ft. "1/4S, NBT"

Witnesses for Corner F2: Red Pine 10 N74°W (mag.) 21.1 ft. "1/4S, NBT"
 (Distances horizontal) Red Pine 10 N73°E (mag.) 47.5 ft. "1/4S, NBT"

Witnesses for Corner 12: W. Pine 8 N48°W (mag.) 10.8 ft. "1/16S, BT"
 W. Pine 6 N17°E (mag.) 6.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 18, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

