

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 40 <sup>N.</sup> <del>XX</del> R. 30 <sup>XX</sup> <del>W.</del>	G 3
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. 40 <sup>N.</sup> <del>XX</del> R. 30 <sup>XX</sup> <del>W.</del>	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G3 (Section Corner 3, 4, 9, & 10, T40N, R30W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Aspen 4 N30E 20 ( " " " " accessories " )  
 Aspen 4 S56W 9 ( " " " " " " )

**Corner 14 (South 1/16 corner between Sections 3 & 4, T40N, R30W):**  
 Not established in original survey and by approximation only, subsequently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G3:** Re-established 6/13/75 by reference to measurements to a monument at Sec. Cor. 4, 5, 8, & 9 to W, a recorded stream bed to E, a recorded stream to S, and the closing corner between Sec. 3 & 4 on the Fourth Correction Line to N. Ties to a stream N are obliterated by pond construction. Corner falls at foot of a hill from S, as in original field notes.  
**Corner 14:** Established 6/16/75 on line between Sec. Cor. 1332.9 ft. S and 1/4 corner 1332.9 ft. N. Found a steel fence post purporting to be this corner S63°E 89.10 ft.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G3:** 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Red Maple 10 S86°E (mag.) 21.8 ft. "S10, NBT"  
 Red Maple 9 N28½°E (mag.) 21.2 ft. "S 3, NBT"  
**Corner 14:** 1" I.D. x 36" iron pipe with 3½" aluminum cap and ½" x 12" re-inforcing rod welded to bottom end.  
 W. Pine 15 N30°E (mag.) 48.4 ft. "1/16S, BT"  
 W. Pine 12 S57°W (mag.) 10.6 ft. "BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 18, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

