

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 40 N. E. R. 30 W.	E3
2. PROPERTY CONTROL- ING IN SECTION _____	T. 40 N. E. R. 30 W.	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E3 (Section Corner 4, 5, 8, & 9, T40N, R30W):
 Wood Post (Not found. Found 1½" I.D. x 36" iron pipe in place.)
 Aspen 4 N81W 19 (Found nail and washer in W. Birch 8 S37°W 14.10 ft.)
 Aspen 5 N7E 11 (" " " " " R. Maple 6 N54°E 17.00 ft.)
Corner 10 (South 1/16 corner between Sections 4 & 5, T40N, R30W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E3: On 6/16/75 replaced monument described above with new monument described below. Existing monument probably placed by Co. Road Comm. personnel c.1934, as it is identical to another reportedly set by them at 1/4 cor. bet. Sec. 4 & 5. Have not ascertained why it was placed here, as it appears to be much farther south than the original survey notes indicate it should be. As it has been much used locally for m/b and probably plat surveys, it seems improper to unsettle these surveys by changing it.
Corner 10: Established 6/13/75 on line between Sec. Cor. 1313.95 ft. S and 1/4 corner 1313.95 ft. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap and 1/2" x 12" re-inforcing rod welded to bottom end.
Witnesses for Corner E3: Red Maple 6 S80°W (mag.) 8.2 ft. "S8, NBT"
 Red Maple 7 S75°E (mag.) 27.4 ft. "S9, NBT"
Witnesses for Corner 10: Red Oak 8 N 6°E (mag.) 4.3 ft. "1/16S, BT"
 Red Maple 5 S84°E (mag.) 7.2 ft. "1/16S, BT"
 Distances horizontal.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 18, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

