

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#K-4
2. PROPERTY CONTROLLING IN SECTION 11 _____	T. 40 N. R. 30 W. <input checked="" type="checkbox"/>	#7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 26, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**Corner K-4 (1/4 corner between Sections 11 & 12, T40N, R30W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Hemlock 12 S12W 10 (Not found. No subsequent accessories found.)  
 Hemlock 18 N34W 8 (Not found. No subsequent accessories found.)

**Corner 7 (North 1/16 corner between Sections 11 & 12, T40N, R30W):**  
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**Corner K-4:** Restored, from a traverse line, on line between Sec. Corners 40.615 ch. to S and to N.  
**Corner 7:** Established, from a traverse line, on line between 1/4 cor. 20.3075 ch. S and Sec. Cor. 20.3075 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**Corner K-4:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 8 N46°W (mag.) 38.9 ft. "1/4S, NBT"  
 Red Maple 6 S67°E (mag.) 42.5 ft. "1/4S, NBT"  
 Declination 2° 55' West.  
**Corner 7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 4 N33°W (mag.) 42.7 ft. "1/16S, BT"  
 ⊕ chiselled in granite outcrop S37°E (mag.) 58.8 ft.  
 Declination 2° 30' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 2, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

