

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code \neq

1. Public Land Survey	T	<u>40N</u>	R	<u>30W</u>	<u>E3</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling In Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	4	5	6	7	8	9	10	11	12	13	14	15	16
4	5	6	7	8	9	10	11	12	13	14	15	16	17
5	6	7	8	9	10	11	12	13	14	15	16	17	18
6	7	8	9	10	11	12	13	14	15	16	17	18	19
7	8	9	10	11	12	13	14	15	16	17	18	19	20
8	9	10	11	12	13	14	15	16	17	18	19	20	21
9	10	11	12	13	14	15	16	17	18	19	20	21	22
10	11	12	13	14	15	16	17	18	19	20	21	22	23
11	12	13	14	15	16	17	18	19	20	21	22	23	24
12	13	14	15	16	17	18	19	20	21	22	23	24	25
13	14	15	16	17	18	19	20	21	22	23	24	25	26

I, Stephen J. Szyszkoski, in a field survey on June 15, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E3) Corner common to Sections 4-5-8-9. Corner re-monumented in 1975 by A.O. Engar, RLS at the location of a found 1 1/4" iron pipe. Set 1" IDx36" iron pipe with 3 1/2" aluminum cap. 1975 NBTs were Red Maple 6 S80W 8.2', Red Maple 7 S75E 27.4'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E3) Found the 1975 1" ID pipe projecting about 8" at record bearing and distance from both 1975 NBTs, blazes overgrown but in good condition. Also found 1 1/2" iron pipe - the previous monument - adjacent. The aluminum cap had been broken off of the 1975 monument but its stem is still fixed firmly in the pipe. Left the monument as found and marked two additional witnesses as described below. Magnetic bearings to the 1975 NBTs are now S84W and S71E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E3) Found 1" iron pipe with remains of aluminum cap in pipe. Blazed and scribed the following new bearing trees:
 7" W. Birch S02W 14.4' "S8 NBT"
 8" Maple in clump of 3 N40E 27.7' (slope distance) "S4 NBT".
 Bearings are magnetic.



Signed by Stephen J. Szyszkoski Date 9-21-94
 Surveyor's Michigan License No. 33986